



## **Addendum II – RFP - 2024-18 – Adler Playground Install (Additional Specifications)**

As requested, the following elements represent the additional specifications for the Adler Playground Equipment Installation.

### **Demolition**

- Provide orange snow fencing around the work site.
- Remove and dispose of all of the playground equipment in (4) of the playgrounds.
- The geodome area is to remain intact.
- Remove and dispose of approximately 730 CY of existing EWF.
- Remove and dispose of 9,800 SF of geofabric, 1-layer.

### **Professional Certified Installation**

- Excavate the new 9,277 SF playground to 12" below finish grade. Reuse the spoils to fill in old playground areas where the EWF will be removed.
- Install all of the playground equipment per the specifications and drawings.
- Install (94) plastic timbers and (1) access wedge.
- Restore all areas disturbed due to construction. Includes backfilling old playground areas with fill dirt as needed prior to installing topsoil, seed and mulch.

12" APS Playground Border with Surfacing Guide and 1 Spike – Quantity 95

APS ADA/Wheelchair accessible Half ramp system, includes 1 half ramp, (2) each 6" filler ends and 4 spikes – Quantity 1

Engineered Wood Fiber – Installed Quantity 430